



**NOZZLE SCHEDULE**

MARK	SIZE	PROJECTION	TYPE	RATING	ELEVATION	ORIENTATION	WELD DETAIL	SERVICE/REMARK
N1	10"	2 3/4"	S/O FLG.	CL-150	ROOF	-	VII, X	RV INLET
N2	3/4"	1 1/4"	CPLG.	CL-3000	16'-6"	180°	IX	WATER MAKE-UP
N3	2"	1 3/4"	CPLG.	CL-3000	0'-3"	90°	IX	DRAIN
N4	2"	7"	S/O FLG.	CL-150	16'-9"	90°	VII, X	OVERFLOW
N5	1 1/2"	1"	WELDMENT	STD.	ROOF	180°	IX	LEVEL BOARD (3)
N6	10"	6 7/8"	PIPE	SCH 40	ROOF	90°	X	VENT
N7	1"	1 1/4"	CPLG.	CL-3000	5'-0"	67.5°	IX	LEVEL TRANSMITTER
N8	2"	-	H-CPLG.	CL-3000	-	-	IX	AMMONIA DETECTOR
N9	2"	1 3/4"	CPLG.	CL-3000	0'-6"	315°	IXa	SIGHT COLUMN
N10	2"	1 3/4"	CPLG.	CL-3000	16'-6"	315°	IXa	SIGHT COLUMN
N11	1"	1 1/4"	CPLG.	CL-3000	12'-11"	270°	IXa	FLOAT
N12	1"	1 1/4"	CPLG.	CL-3000	14'-1"	270°	IXa	FLOAT
M1	2'	5"	DOUBLE-BOLTED MANWAY	U.L.	2'-6"	0°	Xa	W/HANDLES
M2	2'	5"	MANWAY	U.L.	ROOF	225°	X	W/HANDLES

DESIGNED BY - DATE: CMO - 12/10/2024	<b>USEMCO</b> <b>USEMCO INCORPORATED</b> P.O. BOX 550 (608) 372-5911 TOMAH WI. 54660	
DRAWN BY - DATE: EPF - 12/10/2024		
CHECKED BY - DATE: CMO - 12/10/2024	DESCRIPTION: 6,300 GALLON VERTICAL TANK	
SCALE: NTS	DWG. NO.:	99755
<h1>SHEET 2 OF 4</h1>		